


DETAIL OF RAIN WATER HARVESTING
AND RECHARGE PIT (N.T.S.)



DETAIL OF DRAINAGE

SCHEDULE OF DS & WS

TYPE	SIZE	REMARKS
D	1.20 M.X2.10 M.	F PANELED
D1	1.06 M.X2.10 M.	F PANELED
D2	0.91 M.X2.10 M.	F PANELED
W	1.50 M.X1.20 M.	F GLAZED
W1	1.20 M.X1.20 M.	F GLAZED
W2	0.91 M.X1.20 M.	F GLAZED
GATE	1.83 M.X2.10 M.	IRON

SPECIFICATION

- 1 DETAIL OF R.C.C. FOOTING COLUMN FON (M.25)
- 1ST CLASS BRICK WORK IN CEMENT PLASTER (1:6)
- 3 1.25X.15TH. R.C.C. LINTEL BAND OVER DOOR'S & WINDOW'S
- 4 .10TH. LIME CON. TERR.OVER .10TH. R.C.C. ROOF SLAB(M.25)
- 5 SAL WOOD FRAME & SUAM WOOD SHUTTER,
- 6 0.012TH. IN CEMENT PLASTER IN BOTH SIDE WACC (1:6)
- 7 MARBLE OR MOSAIC FLOORING OVER .110TH. DRY RAMMED KHOA OVER B.F. SOILING , OVER LOCAL SAND FILLING .
- 8 2 CUAT OF WHITE & COLOUR WASH AS PER CHOICE.
- 9 17CM.WIDE & 30 CM. PUCCA DRAIN AROUND THE BUILDING .

AREA STATEMENT :-

(1) TOTAL PLOT AREA 9393.56 M²

AREA STATEMENT :-

(1) TOTAL PLOT AREA	9393.56 M ²
(3) TOTAL BUILT UP AREA (G.F.)	1728.08 M ²
(4) TOTAL BUILT UP AREA (F.F.)	1728.08 M ²

SCHOOL BUILDING PLAN OF -
TIRTHANKAR MAHAVEER VIDYA MANDIR,
AT - VEERAYATAN LACHHUAR , SIKANDRA , JAMUI.
(A PROJECT OF VEERAYATAN)
KHATA NO.- 65 , 68 , 182 ,
PLOT NO.-1503 , 1504 , 1518 ,

NAME OF GENERAL MANAGER - MR. ANJANI KUMAR

Deepa K.
Principal
Tirthankar Mahaveer Vidya Mandir
Lachhuar, Sikandra (Jamui)

Anjani Kumar
Anjani Kumar
General Manager
Veerayatan, Bihar

SIGNATURE OF GENERAL MANAGER

Piyush Ranjan
Ar. Piyush Rajeev Ranjan
Empanelment No.-CA/2023/159723
Urban Development & Housing
Department, Patna (Bihar)

SIGNATURE OF ARCHITECT

MAP APPROVED BY

[Signature]
मुजिबा
पंचायत राज, मुल्लों
बखण्ड-सिकंदरा (जमुई)

SIGNATURE OF PASSING AUTHORITY